BRUHAT BANGALORE MAHANAGARA PALIKE
YELAHANKA ZONE

Name of Work: Estimate for Construction of RO Plant in ward No. 05 Byatarayanapura Sub Division

								Est Cost Rs.	1500000.00
Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	ROOM FOR RO PLANT								
1	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, **in ordinary soil** not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 **Page No. 5 / Item No. 2.3 of PWD SR 2016-17**	Cum							
	Centre Line		1	14.44	1.00	1.00	14.44		
	Columns		4	1.35	1.35	1.50	10.94		
							25.38		
							25.38	204.12	**5180.00**
	Basic Rate	189.00							
	Area Weightage @ 8%	15.12							
	Total	**204.12**							
2	KSRB 4-1.3 : Providing and laying in position **plain cement concrete of mix 1:4:8** with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, **in foundation**, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. **Page No.12, Item No. 4.3 of PWD SR 2016-17**	Cum							
	Wall Portion		1	14.44	0.75	0.15	1.62		
			4	1.20	1.20	0.15	0.86		
	For Flooring		1	4.17	2.65	0.15	1.66		
							4.15		
	For 4 Nos						**4.15**	5256.36	**21793.00**
	Basic Rate	4867.00							
	Area Weightage @ 8%	389.36							
	Total	**5256.36**							
3	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in **foundation with cement mortar 1:6, stone** hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 **Page No. 23 / Item No. 5.6, PWD SR 2016-17**	Cum							
	Wall Portion		1	14.44	0.60	0.50	4.33		
	Deduction for Columns		4	1.20	0.60	0.50	-1.44		
							2.89		
							2.89	4521.96	**13078.00**
	Basic Rate	4187.00							
	Area Weightage @ 8%	334.96							
	Total	**4521.96**							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
4	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in **basement with cement mortar 1:6**, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 **Page No. 23 / Item No. 5.9, PWD SR 2016-17**	Cum							
	Wall Portion		1	14.44	0.45	0.45	2.92		
	Deduction for Columns		4	1.20	0.45	0.45	-0.97		
							1.95		
							1.95	5405.40	**10552.00**
	Basic Rate	5005.00							
	Area Weightage @ 8%	400.40							
	Total	**5405.40**							
5	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms, in depth, compacting each deposited layers by ramming after watering with lead upto 50m, and lift upto 1.5m, including cost of all labour complete as per specifications, specification. No. KBS 2.9, **Page No. 6 / Item No. 2.10 / PWD SR 2016-17**	Cum							
			Qty Vide Item No. 1				**25.38**	137.16	**3480.00**
	Basic Rate	127.00							
	Area Weightage @ 8%	10.16							
	Total	**137.16**							
6	KSRB 5-14 : Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 **Page No. 25 / Item No. 5.26.2, PWD SR 2016-17**	Sqm							
	Wall Portion		2	4.57		3.00	27.42		
			2	2.65		3.00	15.90		
	Parapet Wall		2	4.57		0.20	1.83		
			2	2.65		0.20	1.06		
	Steps		2	4.00		0.15	1.20		
							47.41		
	Deductions RS		1	3.00		2.10	6.30		
	V		2	0.90		0.60	1.08		
	Plinth		1	14.44		0.15	2.17		
	Lintels		1	14.44		0.15	2.17		
							-11.71		
							35.70		
							35.70	979.56	**34966.00**
	Basic Rate	907.00							
	Area Weightage @ 8%	72.56							
	Total	**979.56**							
7	Providing and laying **cement concrete** using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete **(RMC) M 20** for R.C.C works laid in 15 cms thick layers and well compacted vibrating, curing, **for raft foundation column footing , main and secondary beams** with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) **Page No. 18, Item No. 4.48, PWD SR 2016-17**	Cum							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	Column Footing		4	1.20	1.20	0.60	3.46		
			4	0.45	0.20	3.50	1.26		
	Plinth Beam		1	14.44	0.20	0.30	0.87		
	Lintels		1	14.44	0.20	0.20	0.58		
	Roof Slab		1	5.47	3.95	0.15	3.24		
							9.40		
							9.40	6349.32	**59690.00**
	Basic Rate	5879.00							
	Area Weightage @ 8%	470.32							
	Total	**6349.32**							
8	KSRB 4.9.2 : Providing **T.M.T steel reinforcement for R.C.C work** including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 **- TMT bars Fe 500 Page No. 17 / Item No. 4.46.2, PWD SR 2016-17**	Tonne							
	For Roof, Columns @ 71 Kg / Cum		0.071	9.40			0.67		
							0.67	65455.56	**43690.00**
	Revised Basic Rate	60607.00							
	Area Weightage @ 8%	4848.56							
	Total	**65455.56**							
9	KSRB 4-6.4 : Providing and removing **centering, shuttering, strutting, propping** etc., and removal of form work for **vertical surface such as walls at any thickness**, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 **Page No. 15 / Item No. 4.31 PWD SR 2016-17**	Sqm							
	Columns Footing		4	4.80		0.60	11.52		
			4	1.30		3.50	18.20		
	Plinth		2	14.44		0.30	8.66		
	Lintels		2	14.44		0.20	5.78		
	Roof		1	4.17	2.65		11.05		
	Roof Extension		2	5.57	0.45		5.01		
			2	3.05	0.45		2.75		
	Sides		2	5.47		0.15	1.64		
			2	3.95		0.15	1.19		
							65.79		
							65.79	316.44	**20820.00**
	Basic Rate	293.00							
	Area Weightage @ 8%	23.44							
	Total	**316.44**							
10	KSRB15-3-13 : Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to **ceiling** including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. **Page No. 114, Item No. 15.21 of PWD SR 2016-17**	Sqm							
			1	4.17	2.65		11.05		
			2	5.57	0.45		5.01		
			2	3.05	0.45		2.75		
							18.81		
							18.81	208.44	**3920.00**
	Basic Rate	193.00							
	Area Weightage @ 8%	15.44							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	Total	**208.44**							
11	KSRB15-3.12 :Providing 20mm thick cement plaster in single coat with cement mortar 1:6, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. **Page No. 114, Item No. 15.21 of PWD SR 2016-17 (Inside Plastering)**	Sqm							
	Inside wall		2	4.17		3.00	25.02		
			2	2.65		3.00	15.90		
							40.92		
	Deductions - For door Doors		0.5x1	3.00		2.10	3.15		
	Door 1		0.5x2	0.90		0.60	0.54		
							-3.69		
							37.23		
							37.23	224.64	**8363.00**
	Basic Rate	208.00							
	Area Weightage @ 8%	16.64							
	Total	**224.64**							
12	KSRB15-7 : Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications. **Page No. 115, Item No. 15.33, PWD SR 2016-17**	Sqm							
			Qty Vide Item No. 39+40				**56.04**	27.00	**1513.00**
	Basic Rate	25.00							
	Area Weightage @ 8%	2.00							
	Total	**27.00**							
13	KSRB15-3.9 :Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. **Page No. 114 / Item No. 15.17, PWD SR 2016-17 (Outside Wall)**	Sqm							
	Out Side		2	4.57		3.00	27.42		
			2	3.05		3.00	18.30		
							45.72		
	Deductions for Door		0.5x1	3.00		2.10	3.15		
	V		0.5x2	0.90		0.60	0.54		
							-3.69		
							42.03		
							42.03	213.84	**8988.00**
	Basic Rate	198.00							
	Area Weightage @ 8%	15.84							
	Total	**213.84**							
14	KSRB 15-14.1 : Providing and **applying two coats with oil bound washable distemper** of approved brand and shade on wall surface including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. **Page No. 117 / Item No. 15.49.1. PWD SR 2016-17**	Sqm							
			Qty Vide Item No.39+40				93.27		
							93.27	76.68	**7152.00**
	Basic Rate	71.00							
	Area Weightage @ 8%	5.68							
	Total	**76.68**							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
15	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. - with primer. **Page No. 117 / Item No. 15.53.2, SR 2016-17.**	Sqm							
				Qty Vide Item No.42			42.03		
							42.03	90.72	**3813.00**
	Basic Rate	84.00							
	Area Weightage @ 8%	6.72							
	Total	**90.72**							
16	KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. (**Page No. 120 Item No. 15.74 of SR 2016-17**).	Sqm							
	Out Side	2.25	1	6.00		2.10	28.35		
			2	0.90		0.60	1.08		
							29.43		
							29.43	88.56	**2606.00**
	Basic Rate	82.00							
	Area Weightage @ 8%	6.56							
	Total	**88.56**							
17	Providing and fixing Special make glazed Vitrified tiles (Granomite finish) of approved make, quality and colour of size 600x600x10mm thick fixed on existing flooring with a special roffe adhesive for flooring and skirting etc., complete including providing spears at required interval and removing stains etc., complete. **(P.No. 107, I.No. 14.43 of SR 2016-17).**	Sqm							
			1	4.17	2.65		11.05		
			2	4.17		0.10	0.83		
			2	2.65		0.10	0.53		
							12.41		
							12.41	1285.20	**15955.00**
	Basic Rate	1190.00							
	Area Weightage @ 8%	95.20							
	Total	**1285.20**							
18	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification. **P.No. 109, I.No. 14.62 of PWD SR 2016-17**	Sqm							
			2	4.00		0.60	**4.80**		
							4.80	1171.80	**5625.00**
	Basic Rate	1085.00							
	Area Weightage @ 8%	86.80							
	Total	**1171.80**							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
19	KSRB 7.7 : Providing and fixing in position in cement concrete 1:3:6 **steel glazed windows and ventilators** side hung/top hung fully openable as per approved drawings using Z angles of 25x33x3mm, weighing 1.419 Kg/m both for outer and inner frames and central mullion section of size 25x46x3mm. weighing 2.28Kg/m duly providing T section 19x19x3mm weighing 0.839 kg/m for glazing of windows not more than 34 cms. c to c including providing and fixing 4mm. thick reeded glass with teakwood beading of required size, all steel sections should confirm to I.S 7452:1990, 4nos. of holdfasts of approved size, section should be cut to length welded and electrically grinded subdividing frames of unit shall be tenonned and revetted into the frames electrically. All the steel surface shall be throughly cleaned free of rust and painted with one coat of anti-corosive paint and finishing with two coats of ready mix paint of approved colour and make including cost of materials, fixtures, labour and HOM of machinery complete as	Sqm							
			2	0.90		0.60	**1.08**		
							1.08	3812.40	**4117.00**
	Basic Rate	3530.00							
	Area Weightage @ 8%	282.40							
	Total	**3812.40**							
20	KSRB 7.5 : Providing and fixing **pull and push type rolling shutters** of approved make out of 18 guage, 75mm wide cold rolled steel laths of convex corrugation, with side guides and bottom rail, with interlocking arrangements for steel laths by means of alternate clips, suspension shaft with High tension coil type springs two numbers, mounted on specially designed pipe shaft, with bracket plates, guide channels, ball bearing arrangements, for inside & outside locking with push & pull operations complete including pulling hooks, 4Nos. handles with all fittings and accessories, painted with a coat of red lead paint (without top cover) cost of materials, labour, HOM of machinery complete as per specifications. **Shutter size 3mx2.8 m**. Specification No. KBS 7.10 / 7.12. (**P.No. 31, I.No. 7.5 of CSR 2016-17**)	Sqm							
			1	3.00		2.10	**6.30**		
							6.30	3090.96	**19473.00**
	Basic Rate	2862.00							
	Area Weightage @ 8%	228.96							
	Total	**3090.96**							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
21	KSRB 7.15 : Providing, fabricating, assembling and fixing in **position aluminium partitions using aluminium sections** of mat finish or classy finish in combination of plain grove, single grove and double grove as per requirements for the frames of overall size 63.5mm x 38.1mm. with thickness of 2mm. having section weight, plain sections 1.054kg/m, single grove thickness 1.95mm. section weight 1.094kg/m, double grove thickness 1.9mm section weight 1.094kg/m and bottom member 114.3 mm. x 44.45mm. thickness 3.18mm. weight 2.646 kg/m; aluminium louvres section of size 36.5mmx34.93mm 1.45mm. thick section weight 0.429kg/m; bottom portions provided with 12mm. thick prelaminated sheet both sides of approved colour lamination exterior grade upto 0.9m height, spacing of vertical member not exceeding 0.6 m. c to c; sections are cut to the required lengths, joints mitered and corners grinded subdividing frames tennoned and rivetted to the frames; the assembled frame stiffened with corner angles, stripped and fixed with screws, rawl plugs and teak wood gutties to R.C.C.columns on sides, R.C.C. lintels or beams at top and floor at bottom, including cutting chistelling and making good with cement mortar	Sqm							
			1	3.00		2.10	**6.30**		
							6.30	3492.72	**22004.00**
	Basic Rate	3234.00							
	Area Weightage @ 8%	258.72							
	Total	**3492.72**							
22	Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including sharing and strutting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strructure manhole. **Page No. 01/ Item No.1.2.2 / PRED SR 2012-13 Hard Soil**	Cum							
			1	20.00	0.45	0.60	5.40		
							5.40	188.00	**1015.00**
	Basic Rate	188.00							
23	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., **Page No.15 item No.3.4.2 b PRED SR 2012-13.**	Rmtr							
	75 mm dia 6 KSC PVC pipe		1	20.00			20.00		
							20.00	157.00	**3140.00**
	Basic Rate	157.00							
24	KSRRB M1200-46. Sand filling in wells complete as per drawing and technical specifications MORTH Specification No.1207 Page No. 213, **Page No. 26.124, PWD SR 2016-17**	Cum							
			1	10.00	0.60	0.30	1.80		
							1.80	2922.42	**5260.00**
	Basic Rate	2757.00							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	Area Weightage @ 6%	165.42							
	Total	**2922.42**							
25	Refilling the basement and pipeline treanches with secleted available earthe for trench excavation including authority condition in layers from thedi including disponsary of the sunplus earth with a heavy 200 mtrs **Page No. 3 / Item No. 1.6 / PRED SR 2012-13**	Cum							
			Qty. Vide Item No. 25-27				**3.60**	61.00	**220.00**
	Basic Rate	61.00							
26	KSRB13-6.3-7 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) **65mm nominal bore** including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.6 / 13.3. **P. No.92 / I. No. 13.38 PWD SR 2016-17**	Each							
			2				**2**	2729.50	**5459.00**
	Basic Rate	2575.00							
	Area Weightage @ 6%	154.50							
	Total	**2729.50**							
27	**10000 LPD R.O. Plant**								
	RAW WATER PUMP:								
	Quantity : 1No.								
	Type: Centrifugal Mono Block								
	MOC & Make : UKL								
	Motor Rating : 0.75 HP								
	PRESSURE SAND FILTER:								
	Quantity : 1No.								
	Capacity : 1000 LPH								
	MOC & Make of Housing : UKL								
	MOC & Make of Cartridge : UKL								
	Capcity : 100 LPH								
	MOC & Make of Vessel : UKL								
	Diameter : 40 mm								
	Type of Valve : Single Multiport								
	media : Support bed + Sand								
	MICRON CARTRIDGE FILTER :								
	Quantity : 1 Set.								
	Filter Rating : 5 Microns								
	Size : 20 " Long								
	ANTISCALANT DOSING PUMPS:								
	Quanity : 1 Set								
	Type : Electro - magnetic								
	Capacity : 1.5 LPH @ 4 Bar								
	HIGH PRESSURE PUMP:								
	Quantity : 1 No								
	Capacity : 1700 LPH								
	Type of Pump : Vertical Multistage Centrigugal Pump								
	MOC : SS 304								
	Motor Rating : 2 HP, 3 Phase								
	Maximum Pressure : 12 Kg/ cm2								
	Make : UKL								
	RESERVE OSMOSIS SYSTEM :								
	Quantity : 1 No								
	Capacity : 1000 LPH								
	Module Type								
	Membrane Specifications {Polyamde}								
	Make of Membrane : UKL								
	UV STERILISER								
	Max. Treatment Flow : 1 m3/hr								
	No. of Lamps : 1 No								

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	Wattage : 39 W								
	Efficiency : 99.99%								
	Material of Construction : SS 304								
	PRODUCT WATER QUALITY:								
	Appearance : Crystal Clear								
	Abide by the ISO Standards								
	S S Tank : 304 Grade with 16 guage 2000 liters Capacity								
	304 Grade 10 Gauage SS Pipe {with stream valve} 25 Ft								
	COIN BOOTH DISPENSING UNIT								
	for 5 Liters & 20 Ltrs Separately								
	Raw Water Stoage Tank : Dunction - for Storage of Raw Water								
	Type / MOC : Two / Three Layered PE tanks White / Transparent in color made from virgin material of food grade Quality suitabke fir the purpose of providing								
	Storage Drinking / Portable Water : 5000 Liters Capacity	Nos							
			1				**1**	946000.00	**946000.00**
	Approved DATA Rate	946000.00							
	ELECTRIFCATION								
28	Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 1100V grade, COPPER conductor flexible multistrand FRLS PVC insulated, 2 X1.5Sq.mm Cable confirming to the GTP, with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet / gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. GROUP A b) Medium point above 3Mtr upto 6Mtr from tapping point to out let via switch **(Page No. 05, Item No.2.1 KPWD SR 2014-15**	Point							
			1x6				**6**	245.00	**1470.00**
29	c) Long point above 6Mtr upto 10Mtr from tapping point to out let via switch	Point	1x6				**6**	363.00	**2178.00**
30	Supplying and flush mounting teak wooden box without front plank, made of not less than 12mm thick wood, after due groove cutting, Finishing with necessary cement plastering complete (1.6.5) 4"x4"x3" (101x101x76mm) **(Page No. 03, Item No. 1.6) KPWD SR 2014-15**	Each							
			1x30				**30**	68.00	**2040.00**
31	(1.6.1) 12"x12"x3" (300x300x76mm)	Each	1x18				**18**	116.00	**2088.00**
32	(1.6.3)10"x7"x3" (254x178x76mm)	Each	1x15				**15**	87.00	**1305.00**
33	Supplying 4mm thick plastic sheet with necessary nitches for fixing switches, regulators etc., and fixing on existing wooden or metal box using N.F. screws. **(Page No. 17, Item No. 3.9) KPWD SR 2014-15**	SqCM							
							33333	0.25	**8333.00**
34	Extra for Groove cutting in brick wall/CC floor to the suitable depth for concealing of Conduit/GI pipe and plastering, finishing upto wall surface complete. upto 50mm conduit in brick wall **(Page No. 03, Item No.1.7.1) KPWD SR 2014-15**	Mtr							
			1	20.00			**20**	21.00	**420.00**

Description of item	Unit	No	L	B	D	Qty	Rate	Amount
Supplying heavy gauge PVC Conduit Pipe 19/20 mm dia 2 mm thick with suitable size bends, metal junction boxes adhesive paste etc., by groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the wall surface and run with 18 SWG GI fish wire run throughout the conduit wherever necessary. **(Page No. 02, Item No. 1.3.1) KPWD SR 2014-15**	Mtr							
		1	20.00			**20**	56.00	**1120.00**
Supplying and fixing PBBC/Bakelite straight or slant batten holder and wiring with 60w/230 volts lamps. **(Page No. 20, Item No. 4.2) KPWD SR 2014-15**	Each							
		1x4				**4**	88.00	**352.00**
Supplying patti type fluorescent tube light fitting of 2' - suitable for 14 watts fluorescent tube fitting, made out of M.S. Sheet and stove enameled with HF Electronic Ballast , locking type brass contact holders mounted on double fold type sheet base fully wired for use on 230 volts AC . Supply including T5 lamp. **(Page No. 20, Item No. 4.5) KPWD SR 2014-15**	Each							
		1x4				**4**	591.00	**2364.00**
Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper with low conductor resistance single core wire in open or concealed system of wiring with specified IS-694:1990 & confirming to GTP of GROUP -A 1.5 sqmm **(Page No. 06, Item No. 2.5.2) KPWD SR 2014-15**	Mtr							
		1	15.00			**15**	18.60	**279.00**
Supplying and fixing cast Aluminum round or oblong type bulk head fitting with GI wire guard, glass cover with 60/100 watts 230V GLS lamp. **(Page No. 20, Item No. 4.3) KPWD SR 2014-15**	Each							
		1x8				**8**	747.00	**5976.00**
Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia **(Page No. 55, Item No. 7.1) KPWD SR 2014-15**	No							
		1				**1**	2727.00	**2727.00**
1 Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A **P No. 55/ I No. 7.4.4 4 core 16 Sqmm KPWD Electrical SR 2014-15**	Mtr							
		1	25.00			**25.00**	140.40	**3510.00**

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
42	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.In existing trench/duct. **P No. 61 / I No. 7.8.1 6Sqmm to 16 Sqmm) KPWD Electrical SR 2014-15**	Mtr	1	25.00			**25.00**	10.80	**270.00**
43	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete For Cutting Road Surface .(As per Civil SR KSRB I-2, P-7) **P No. 61 / I. No. 7.9.3 KPWD Electrical SR 2014-15**	Mtr	1	20.00			**20.00**	85.00	**1700.00**
44	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV 40mm dia GI pipe **P. No. 62 / I No. 7.12.1 KPWD Electrical SR 2014-15**	Mtr	1	4.00			**4.00**	345.00	**1380.00**
45	Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers 16Sqmm etc., **P. No. 62 / I.No. 7.13.2 KPWD Electrical SR 2014-15**	No.	1				**1.00**	280.00	**280.00**
	Sub Total								**1315664.00**
	GST @ 12%								**157880.00**
	Borewell BESCOM Deposit		1	16000.00					**16000.00**
	RO Plan BESCOM Deposit		1	10000.00					**10000.00**
	Miscellaneous and Unforeseen Charges	L/S							**456.00**
								Total	**1500000.00**

#NAME?

CERTIFICATE:

1 The work spot has been inspected and the work is found necessary.
2 This estimate is prepared as per C.S.R. of PWD 2016-17, PWD Elecrical 2014-15, PRED 2012-13 & approved Rate.
3 The provisions were made in this estimate are necessary and adequate.
4 This works come under B.B.M.P. limits.

Assistant Engineer
Ward No. 05

Assistant Executive Engineer
Bruhat Bangalore Mahanagara Palike
Byatarayanapura Sub Division

Executive Engineer
Bruhat Bangalore Mahanagara Palike,
Byatarayanapura Division

Administrative Approval
Accorded For RS. 15.00 lakhs
Head of A/C P 3445
CER NO :AS/175/18-19 Dt. 09.1.2019

TA CE (YNK)

TECHNICAL SANCTION
Accorded For Rs. Fifteen lakhs only
Head of A/c. P-3445
Div. Ref. No. 115 Date 21/02/19

AE 21/02 EE(BTP) 21/02